BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18538/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Improvements of Roads and Drains at Shabarinagara in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAVEEN KUMAR N		
				In Figures		In Words
1	900	KSRRB 300-1. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 126/ Item No. 19.2/ PWD SR 2011-12 For Rachenahalli Tank	Cum	110.0	99000.00	Rupees One Hundred Ten Only
2	900	Hegadenagara 5th Cross	Cum	110.0	99000.00	Rupees One Hundred Ten Only
3	2690	Code 0516- Providing Palstic Sheet (Page No.XXII/1.612 PWD SR 2014-15For Rachenahalli Tank	Sqm	6.0	16140.00	Rupees Six Only
4	487.2	Providing Stone dust to approch road and near immerssion tank for levelling and to protect not to sliping SI No.23 Code 400 Metal Component Page No I SR 2010-11 For Rachenahalli Tank	Cum	730.0	355656.00	Rupees Seven Hundred Thirty Only
5	35	Hire Charge of Pumping water 3.5 KL/hr Capacity Pump For Rachenahalli Tank	Hr	50.0	1750.00	Rupees Fifty Only
6	35	Hegadenagara 5th Cross	Hr	50.0	1750.00	Rupees Fifty Only
7	450	Engaging unskilled heavy Mazdoor labour for Guarding and for helping the public to Immersion tank Ganesh Idols and to safe guard the public during the pooja Time For Rachenahalli Tank	Days	200.0	90000.00	Rupees Two Hundred Only
8	450	Hegadenagara 5th Cross	Days	200.0	90000.00	Rupees Two Hundred Only
9	1750	Hire Charges for Shamiyana Side wall of 8ft Hight (Size175 Rft) For Rachenahalli Tank	Rmt	16.0	28000.00	Rupees Sixteen Only
10	1750	Hegadenagara 5th Cross	Rmt	16.0	28000.00	Rupees Sixteen Only
11	150	Hire Charges for Armless Plastic Charis For Rachenahalli Tank	No	4.0	600.00	Rupees Four Only
12	150	Hegadenagara 5th Cross	No	4.0	600.00	Rupees Four Only
13	150	Hire Charges for Wooden Table of size 6ft x 2ft For Rachenahalli Tank	No	35.0	5250.00	Rupees Thirty Five Only
14	150	Hegadenagara 5th Cross	No	35.0	5250.00	Rupees Thirty Five Only
15	1100	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 sqmm PVC insulated and sheathedaluminium wire (KPWD Electrical SR 2011-12 P.55/I.6 III b) For Rachenahalli Tank	Day	9.0	9900.00	Rupees Nine Only
16	1100	Hegadenagara 5th Cross	Day	9.0	9900.00	Rupees Nine Only
17	80	1321 Hire charge of 100 KVA Generator including operator.Fuel transporation nd Handling charges PWD SR 2011-12 XVI/I.92)For Rachenahalli Tank	Hr	620.0	49600.00	Rupees Six Hundred Twenty Only
18	80	Hegadenagara 5th Cross	Hr	620.0	49600.00	Rupees Six Hundred Twenty Only
19	20	Hire Charges for Flood Lighting Arrangements for the stage and existing Immersion Tank during night time For Rachenahalli Tank	Each	250.0	5000.00	Rupees Two Hundred Fifty Only
20	20	Hegadenagara 5th Cross	Each	250.0	5000.00	Rupees Two Hundred Fifty Only
21	3432	Hire Charges for Three Tier Barricading with Casurens poles at 2.50mtrs C/C Vertically and 0.50 mtrs C/C Horizontally with Necessary earth work and labour For Rachenahalli Tank	Rmt	16.0	54912.00	Rupees Sixteen Only
22	3432	Hegadenagara 5th Cross	Rmt	16.0	54912.00	Rupees Sixteen Only
23	13200	Hire Charge for Shamiyana with Necessary Bambo Poles.Erection charges including transportation -(Size: 40ft x30ft=1200 sqft) For Rachenahalli Tank	Sft	3.0	39600.00	Rupees Three Only
24	13200	Hegadenagara 5th Cross	Sft	3.0	39600.00	Rupees Three Only
25	25	Hire Charge of Pumping water 3.5 KL/hr Capacity Pump For Rachenahalli Tank	Hr	50.0	1250.00	Rupees Fifty Only
26	25	Hegadenagara 5th Cross	Hr	50.0	1250.00	Rupees Fifty Only

Naveen Kumar.N

26/7/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAVEEN KUMAR N		
				In Figures		In Words
27	113	Retro - Reflectorised Traffic Signs :- Providing and fixing of retro - reflectorised cautionary, mandatory and informatory sign as per IRC : 67 - 2001 made of high intensity grade micro prismatic HIP type IV sheeting, fixed over alumium sheeting, 12 gauge thick supported on 75mm dia and 4mm thick MS pipe 2.8 mtres long firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 45cms x 45cm x 60cm, 60 cm below ground level as per approved drawing. The item includes earthwork excavation, Cement Concrete M-15 grade, 2 coats of approved colour synthetic enamel painting to the steel surface, as per clauses, including curing, cost of all materials, labour, loading, unloading, lead, lift, transporting etc., complete. (P.No.65, H.No.8.04 of NH SR 2009-10)	Each	3301.04	373017.52	Rupees Three Thousand Three Hundred One and Four Paise Only
					1514537.52	

Naveen Kumar.N

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

29/7/16

20/07